BRUHATH BANGALORE MAHANAGARA PALIKE ,DASRAHALLI ZONE

Office Of The Executive Engineer, Dasarahalli Division

SCHEDULE-B

NAME OF THE WORK: Improvements of CC drains & Covering Slab KK road 2nd and 3rd cross Dasarahalli Ward No-15

SI No	Description Of Work	Unit	Qty	Rate To Be Sanctioned	
				In Figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. C. Prestressed / Reinforced cement concrete grade M-20 & above.	Cum	161.10	1400.00	Rupees One Thousand Four Hundred Only
2	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil invoiving , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification	Cum	429.60	100.00	Rupees One Hundred Only
3	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications.	Cum	42.96	5000.00	Rupees Five Thousand Only
4	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specificationsdo- Wall & bottom thickness 15cm	Tonne	128.88	7000.00	Rupees Seven Thousand Only

Signature Of The Contractor

Executive Engineer
Dasarahalli Division

Scanned by CamScanner

	Description Of Work	Unit	Qty	Rate To Be Sanctioned	
				In Figures (Rs)	In Words (Rs)
1	2	3	4	5	6
5	Supplying and Fixing pre cast Reinforced Concrete Slab 10cm thick, including cost of reinforcement as per design and drawing,materials cost,transportation,hire charges of machinery,machine cutting the verticle face to get plain even surface etc...complete with all leads and lift conveyance charges,labour charges,inclusive of cost of all materials (Data Rate)	Sqm	322.20	2100.00	Rupees Two Thousand One Hundred Only
6	Supplying, fitting and placing TMT bar reinforcement in sub-structure complete as per drawing and Technical Specifications complete as per specifications		10.31	70000.00	Rupees Seventy Thousand Only
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work,lead 4km a) basic rate for haulage of materials as per item No.17.4/KSRRB:M100-4.1...RS.2.00 Tonne/km b)average earth of work 1.28 tonne/km for Rs.2.00/km. c)Add Loading and Unloading	Cum	480.00	68.80	Rupees Sixty Eight And Paise Eighty Only

Signature Of The Contractor

Executive Engineer
Dasarahalli Division

Scanned by CamScanner